



BID TABULATION
Potter Tract Road - Replacement of Structure #108
RA49-05-26 / MCP-004-22
Mobile County, Alabama
Wednesday, August 12, 2026 @ 10:00 A.M.

ITEM	DESCRIPTION	QTY	UNIT	Murphree Bridge Corporation	
				UNIT PRICE	AMOUNT BID
201C000	Clearing	1	Lump Sum	\$ 10,000.00	\$ 10,000.00
206A000	Removal Of Old Bridge, Station 102+81.22 TO Station 103+71.22	1	Lump Sum	\$ 70,000.00	\$ 70,000.00
206D001	Removing Guardrail	40	Linear Foot	\$ 2.00	\$ 80.00
206E008	Removing Guardrail End Anchor (All Type)	8	Each	\$ 325.00	\$ 2,600.00
210A000	Unclassified Excavation (Loose Truckbed Measurement)	500	Cubic Yard	\$ 29.18	\$ 14,590.00
210D022	Borrow Excavation (Loose Truckbed Measurement)(A-2-4(0) or A-4(0))	600	Cubic Yard	\$ 36.40	\$ 21,840.00
230A000	Roadbed Processing	4	Station	\$ 645.40	\$ 2,581.60
301A012	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness	700	Square Yard	\$ 45.43	\$ 31,801.00
401A000	Bituminous Treatment A	700	Square Yard	\$ 0.01	\$ 7.00
405A000	Tack Coat	70	Gallon	\$ 0.01	\$ 0.70
424A360	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D	100	Ton	\$ 169.26	\$ 16,926.00
424B651	Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D	150	Ton	\$ 169.26	\$ 25,389.00
505A015	Concrete Test Piles (14 Inches Square)	2	Each	\$ 16,000.00	\$ 32,000.00
505B045	Static Loading Tests (14 Inches Square)	2	Each	\$ 39,000.00	\$ 78,000.00
505G000	Temporary Steel Sheet Piling	1680	Square Foot	\$ 35.00	\$ 58,800.00
505A000	Concrete Piling Furnished (14 Inches Square)	1857	Linear Foot	\$ 160.00	\$ 297,120.00
505D000	Concrete Piling Driven (14 Inches Square)	1857	Linear Foot	\$ 1.00	\$ 1,857.00
507A000	Wire Rope Abutment Anchor Assembly	2	Each	\$ 22,500.00	\$ 45,000.00
511A000	Elastomeric Bearing Type 1	44	Each	\$ 200.00	\$ 8,800.00
512A014	Precast Concrete Abutment Caps, 2'-0" Wide By 1'-8" Deep By 33'-0" Long	2	Each	\$ 12,300.00	\$ 24,600.00
512B004	Precast Concrete Intermediate Bent Caps, 2'-0" Wide By 2'-0" Deep By 31'-6" Long	2	Each	\$ 14,500.00	\$ 29,000.00
512C004	Precast Concrete Type 1 Span Section, 3'-6" Wide By 1'-9" Deep By 34'-0" Long	18	Each	\$ 12,700.00	\$ 228,600.00
512C007	Precast Concrete Type 2C Span Section, 3'-6" Wide By 1'-9" Deep By 34'-0" Long	6	Each	\$ 13,100.00	\$ 78,600.00
512D002	Precast Concrete Barrier Rail End Section, 34'-0" Long	4	Each	\$ 14,000.00	\$ 56,000.00
512D005	Precast Concrete Barrier Rail Intermediate Section, 34'-0" Long	2	Each	\$ 14,200.00	\$ 28,400.00
512E001	Precast Concrete Abutment Panels, Type A2	16	Each	\$ 1,100.00	\$ 17,600.00
512F001	Precast Concrete Wing Panels, Type W2	8	Each	\$ 2,000.00	\$ 16,000.00
512G000	Precast Concrete Abutment Wing Cap Panels	4	Each	\$ 1,600.00	\$ 6,400.00
600A000	Mobilization	1	Lump Sum	\$ 138,991.66	\$ 138,991.66
610A004	Loose Riprap, Class 2, 24" Thick	550	Square Yard	\$ 85.00	\$ 46,750.00
6100003	Filter Blanket, Geotextile	550	Square Yard	\$ 6.00	\$ 3,300.00
620A000	Minor Structure Concrete	3	Cubic Yard	\$ 200.00	\$ 600.00
630C002	Guardrail End Anchor, Type 13	4	Each	\$ 3,200.00	\$ 12,800.00

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT BID
630C080	Guardrail End Anchor, Type 20 Series (MASH)	4	Each	\$ 3,800.00	\$ 15,200.00
650A000	Topsoil	175	Cubic Yard	\$ 37.40	\$ 6,545.00
654A001	Solid Sodding (Bermuda)	1400	Square Yard	\$ 7.00	\$ 9,800.00
665E000	Polyethylene	1500	Square Yard	\$ 3.50	\$ 5,250.00
665G000	Sand Bags	100	Each	\$ 8.17	\$ 817.00
665J002	Silt Fence	800	Linear Foot	\$ 5.84	\$ 4,672.00
665L000	Floating Basin Boom	200	Linear Foot	\$ 23.35	\$ 4,670.00
665O001	Silt Fence Removal	800	Linear Foot	\$ 1.17	\$ 936.00
665Q001	Wattle	400	Linear Foot	\$ 10.51	\$ 4,204.00
680A001	Geometric Controls	1	Lump Sum	\$ 8,125.63	\$ 8,125.63
698A000	Construction Fuel (Maximum Bid Limited to \$25,000)	1	Lump Sum	\$ 1,500.00	\$ 1,500.00
701C001	Solid Temporary Traffic Stripe	1	Mile	\$ 1,600.00	\$ 1,600.00
701G093	Solid White, Class 3, Type A Traffic Stripe	250	Linear Foot	\$ 10.00	\$ 2,500.00
701G094	Solid Yellow, Class 3, Type A Traffic Stripe	250	Linear Foot	\$ 10.00	\$ 2,500.00
701A227	Solid White, Class 2, Type A Traffic Stripe (5" Wide)	1	Mile	\$ 3,800.00	\$ 3,800.00
701A230	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)	3	Mile	\$ 3,800.00	\$ 11,400.00
703A000	Traffic Control Markings, Class 2, Type A	48	Square Foot	\$ 5.00	\$ 240.00
705A001	Pavement Markers, Class A, Type 1-A	150	Each	\$ 6.00	\$ 900.00
705A005	Pavement Markers, Class A, Type 2-D	150	Each	\$ 6.00	\$ 900.00
710C000	Removal Of Existing Roadway Signs	1	Lump Sum	\$ 5,750.00	\$ 5,750.00
711G000	Roadway Sign Relocation	1	Lump Sum	\$ 1,050.00	\$ 1,050.00
740B000	Construction Signs	366	Square Foot	\$ 8.00	\$ 2,928.00
740D000	Channelizing Drums	75	Each	\$ 38.00	\$ 2,850.00
740E002	Cones (36 Inches High)	75	Each	\$ 1.00	\$ 75.00
740F002	Barricades, Type III	8	Each	\$ 215.00	\$ 1,720.00
740I000	Warning Lights, Type B	16	Each	\$ 65.00	\$ 1,040.00
742A001	Portable Changeable Message Sign, Type 2	2	Each	\$ 3,200.00	\$ 6,400.00
Total Bid					\$ 1,512,406.59

Certified:



Garrett Jacobs, P.E.