TABULATION OF BIDS
DAUPHIN ISLAND STREET RESURFACING MCR-2018-303
FOR THE MOBILE COUNTY COMMISSION
GMC PROJECT NO. CMOB190203

BID OPENING: WEDNESDAY, November 6, 2019 10:00 A.M.

				H. O. Weaver & Sons Inc. Mobile, AL		John G. Walton Construction Company Mobile, AL		HCL Contracting LLC Semmes, AL	
Item No.	Qty.	Unit	Description	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price
212-A	182	STA	MACHINE GRADING SHOULDERS	$ 48.87	$ 8,894.34	$ 26.00	$ 4,732.00	$ 84.00	$ 15,288.00
405-A	1,576	GAL	TACK COAT	$ 3.73	$ 5,878.48	$ 3.65	$ 5,752.40	$ 6.00	$ 9,456.00
408-A	1,004	SY	PLANING EXISTING PAVEMENT (APPROX. 1.5" THICK)	$ 7.85	$ 7,881.40	$ 6.49	$ 6,515.96	$ 13.00	$ 13,052.00
424-A1	1,926	TONS	SUPERPAVE BITUMINOUS CONCRETE WEARING SURFACE LAYER, 1/2" MAXIMUM AGGREGATE SIZE MIX, ESAL RANGE A/B (APPROX. 165 LBS/SY)	$ 92.00	$ 177,192.00	$ 109.58	$ 211,051.08	$ 109.00	$ 209,934.00
424-A2	25	TONS	SUPERPAVE BITUMINOUS CONCRETE WEARING SURFACE LAYER, PATCHING, 1/2" MAXIMUM AGGREGATE SIZE MIX, ESAL RANGE A/B(APPROX. 330 LBS/SY)	$ 179.35	$ 4,483.75	$ 143.80	$ 3,595.00	$ 136.00	$ 3,400.00
600-A	1	LS	MOBILIZATION	$ 26,436.69	$ 26,436.69	$ 20,726.00	$ 20,726.00	$ 9,820.00	$ 9,820.00
641-S	1	EACH	VALVE BOX RESET	$ 332.13	$ 332.13	$ 120.98	$ 120.98	$ 210.00	$ 210.00
645-K	16	EACH	MANHOLE FRAME AND COVER RESET	$ 370.50	$ 5,928.00	$ 392.25	$ 6,276.00	$ 428.00	$ 6,848.00
650-A	415	CUYD	TOPSOIL	$ 36.77	$ 15,259.55	$ 0.01	$ 4.15	$ 36.00	$ 14,940.00
652-A	3	ACRE	SEEDING	$ 1,666.65	$ 4,999.95	$ 1,996.61	$ 5,989.83	$ 1,717.00	$ 5,151.00
656-A	3	ACRE	MULCHING	$ 1,666.65	$ 4,999.95	$ 1,357.71	$ 4,073.13	$ 1,177.00	$ 3,531.00
680-A	1	LS	GEOMETRIC CONTROLS	$ 2,792.66	$ 2,792.66	$ 2,276.30	$ 2,276.30	$ 3,300.00	$ 3,300.00
698-A	1	LS	CONSTRUCTION FUEL (MAXIMUM BID LIMITED TO $3,500)	$ -	$ -	$ -	$ -	$ -	$ -
703-A	188	SF	TRAFFIC CONTROL MARKINGS, CLASS 2, TYPE A	$ 5.56	$ 1,045.28	$ 5.50	$ 1,034.00	$ 10.00	$ 1,880.00
703-D	188	SF	TEMPORARY TRAFFIC CONTROL MARKINGS	$ 2.22	$ 417.36	$ 2.20	$ 413.60	$ 3.00	$ 564.00
740-B	519	SF	CONSTRUCTION SIGNS	$ 0.01	$ 5.19	$ 9.08	$ 4,712.52	$ 0.01	$ 5.19
740-D	135	EACH	CHANNELIZING DRUMS	$ 0.01	$ 1.35	$ 0.01	$ 1.35	$ 0.01	$ 1.35
740-E	135	EACH	CONES (36" HIGH)	$ 0.01	$ 1.35	$ 0.01	$ 1.35	$ 0.01	$ 1.35
740-M	135	EACH	BALLAST FOR CONES	$ 0.01	$ 1.35	$ 0.01	$ 1.35	$ 0.01	$ 1.35
					$ 266,550.78		$ 277,277.00		$ 297,383.24

Patrick R. Strom II, PE, License No. 32817

ALABAMA LICENSED No. 32817 PROFESSIONAL ENGINEER PATRICK ROBERT STROM II