BID TABULATION

MOBILE COUNTY

PROJECT NO. CIP-2013-013
GRAND BAY WILMER ROAD LENGTHING AND REPAIR OF BRIDGE STRUCTURE #2
MOBILE COUNTY, AL
MAY 2, 2014

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	CONTRACTOR		ENGINEER'S ESTIMATE	
				Gulf Equipment			
				UNIT COST	COST	UNIT COST	COST
201A002	CLEARING AND GRUBBING (MAXIMUM ALLOWABLE BID $4000 PER ACRE) (APPROXIMATELY 1.0 ACRES)	LS	1	$4,000.00	$4,000.00	$4,000.00	$4,000.00
206A050	REMOVAL OF OLD BRIDGE, PARTIAL, STATIONS 239+93.18 TO 240+17.20	LS	1	$15,001.89	$15,001.89	$30,000.00	$30,000.00
206C023	REMOVING RIPRAP	SQ YD	75	$34.77	$2,607.75	$15.00	$1,125.00
210A000	UNCLASSIFIED EXCAVATION	CU YD	368	$9.50	$3,496.00	$12.35	$4,545.34
230A000	ROADBED PROCESSING	RBST	1	$1,175.51	$1,175.51	$172.47	$172.47
301A012	CRUSED AGGREGATE BASE COURSE, TYPE B, PLANT MIXED, 6" COMPACTED THICKNESS	SQ YD	148	$19.06	$2,820.88	$23.10	$3,418.65
401A000	BITUMINOUS TREATMENT A	SQ YD	145	$2.39	$346.55	$1.87	$271.54
504G001	STEEL PILING ENCASEMENT, DRY CONDITION	LIN FT	56	$170.88	$9,569.28	$100.00	$5,600.00
505A002	STEEL TEST PILES (HP 12X53)	EACH	2	$8,944.60	$17,889.20	$30,000.00	$60,000.00
505B057	STATIC LOADING TESTS (HP 12X53)	EACH	2	$1,141.75	$2,283.50	$3,142.53	$6,285.06
505B087	DYNAMIC LOADING TESTS (HP 12x53)	EACH	2	$5,716.97	$11,433.94	$1,765.74	$3,531.49
505M002	STEEL PILING, FURNISHED AND DRIVEN (HP 12X53)	LIN FT	865	$55.80	$48,267.00	$42.43	$36,702.26
511A000	ELASTOMERIC BEARING TYPE 1	EACH	24	$116.66	$2,799.84	$200.00	$4,800.00
512A024	PRECAST CONCRETE ABUTMENT CAPS,2'-0" WIDE BY 1'-8 29/64" DEEP BY 40'-0" LONG (MODIFIED)	EACH	1	$9,080.68	$9,080.68	$10,000.00	$10,000.00
512B027	PRECAST CONCRETE INTERMEDIATE BENT CAPS,2'-0" WIDE BY 1'-8 29/64" DEEP BY 40'-0" LONG (MODIFIED)	EACH	1	$12,785.15	$12,785.15	$10,000.00	$10,000.00
512C002	PRECAST CONCRETE TYPE 1 SPAN SECTION, 3'-6" WIDE BY 1'-5" DEEP BY 24'-0" LONG	EACH	14	$2,585.70	$36,199.80	$3,500.00	$49,000.00
512C006	PRECAST CONCRETE TYPE 2C SPAN SECTION, 3'-6" WIDE BY 1'-5" DEEP BY 24'-0" LONG	EACH	4	$2,673.97	$10,695.88	$4,000.00	$16,000.00
512D001	PRECAST CONCRETE BARRIER RAIL END SECTION, 24'-0" LONG	EACH	2	$3,337.48	$6,674.96	$3,500.00	$7,000.00
512D004	PRECAST CONCRETE BARRIER RAIL INTERMEDIATE SECTION, 24'-0" LONG	EACH	2	$3,342.29	$6,684.58	$3,500.00	$7,000.00
600A000	MOBILIZATION	LS	1	$68,590.50	$68,590.50	$20,000.00	$20,000.00
610C001	LOOSE RIPRAP, CLASS 2	TON	499	$61.90	$30,888.10	$57.76	$28,820.62
610D003	FILTER BLANKET, GEOTEXTILE	SQ YD	414	$2.41	$997.74	$4.14	$1,713.02
631F001	STEEL BEAM GUARDRAIL, CLASS A, TYPE 2 RELOCATED	LIN FT	63	$17.25	$1,086.75	$10.00	$630.00
631G013	GUARDRAIL END ANCHOR, TYPE 13, RELOCATED	EACH	2	$868.25	$1,736.50	$632.38	$1,264.75
631G015	GUARDRAIL END ANCHOR, TYPE 20 SERIES, RELOCATED	EACH	2	$1,097.10	$2,194.20	$1,006.34	$2,012.68
650A000	TOPSOIL	CU YD	46	$15.36	$706.56	$18.13	$834.19
652A100	SEEDING	ACRE	1	$1,143.70	$1,143.70	$992.24	$992.24
654A001	SOLID SODDING (BERMUDA)	SQ YD	160	$6.15	$984.00	$5.00	$800.01
656A010	MULCHING	ACRE	1	$1,459.95	$1,459.95	$713.14	$713.14
659C002	EROSION CONTROL PRODUCT, TYPE S2	SQ YD	428	$6.00	$2,568.00	$1.61	$689.59

BID TABULATION

MOBILE COUNTY

PROJECT NO. CIP-2013-013
GRAND BAY WILMER ROAD LENGTHING AND REPAIR OF BRIDGE STRUCTURE #2
MOBILE COUNTY, AL
MAY 2, 2014

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	CONTRACTOR		ENGINEER'S ESTIMATE	
				Gulf Equipment			
				UNIT COST	COST	UNIT COST	COST
665A000	TEMPORARY SEEDING	ACRE	2	$970.61	$1,941.22	$327.41	$654.82
665B001	TEMPORARY MULCHING	TON	4	$729.97	$2,919.88	$321.37	$1,285.49
665J002	SILT FENCE	LIN FT	716	$4.32	$3,093.12	$3.16	$2,263.55
665L000	FLOATING BASIN BOOM	LIN FT	93	$15.45	$1,436.85	$14.13	$1,314.07
665O001	SILT FENCE REMOVAL	LIN FT	716	$0.52	$372.32	$0.89	$639.70
666A001	PEST CONTROL TREATMENT	ACRE	1	$575.00	$575.00	$58.19	$58.19
680A001	GEOMETRIC CONTROLS	LS	1	$2,037.11	$2,037.11	$40.00	$40.00
698A000	CONSTRUCTION FUEL (MAXIMUM BID LIMITED TO $11,100)	LS	1	$0.01	$0.01	$11,000.00	$11,000.00
740B000	CONSTRUCTION SIGNS	SQ FT	316	$14.95	$4,724.20	$7.12	$2,248.87
740D000	CHANNELIZING DRUMS	EACH	50	$30.75	$1,537.50	$27.24	$1,362.02
740F002	BARRICADES, TYPE III	EACH	8	$212.75	$1,702.00	$231.84	$1,854.72
740I002	WARNING LIGHTS, TYPE B	EACH	8	$143.75	$1,150.00	$171.52	$1,372.16
TOTAL					**$337,657.60**		**$342,015.66**

I, Andrew E. James, Project Manager, Volkert, Inc., Consulting Engineers,do hereby certify that this tabulation of bids received by the Mobile County Engineering Department'on 4/30/14 for construction of the herein referenced project,is a true and correct copy of the bids submitted by the within named corporations.

Andrew E. James, Project Manager

Volkert, Inc.